

DOCUMENT 00910

**ADDENDA**

**CONTRACT NUMBER 12-22-2  
STOCKTON PORT DISTRICT  
AUXILIARY WATER LINE IMPROVEMENTS  
ADDENDUM NO. 1  
January 27, 2023**

This Addendum No. 1 {"Addendum"} is dated the date set forth above and modifies certain Bidding Documents issued by the Stockton Port District {"Port"} in connection with the Port's **AUXILIARY WATER LINE IMPROVEMENTS, CONTRACT No. 12-22-2**. All capitalized terms not otherwise defined herein shall have the meanings provided in the Bidding Documents. There are no other amendments to the Bidding Documents other than those which are expressly contained in this Addendum.

---

**DIRECTIVES:**

1. Project Plans, Sheet 7 - 8, Add –
  - Two (2) 4-inch HDPE SDR 9 conduit, 643 linear feet to be installed simultaneously with 16-inch HDPE SDR 9 water pipe. 4" Pipes to have Orange stripe for communications.
  - Install two (2) 3 feet by 4 feet pull box at each end of conduit. Station 100+00 and Station 106+43.
2. Section 00400-2, Bid Form, Add item 17, Connect to existing fire water, Sta 99+90.
3. Section 00400-2, Bid Form, Add item 19, Furnish and install (2) 4-inch, SDR 9 Conduit, Sta. 100+00 – 160+43
4. Section 00400-2, Bid Form, Add item 20, Furnish and install 3'x4' pull box at Approximate Sta. 100+00 and 160+43.
5. Section 01100-A-4, Technical Specifications, Add paragraph 1.0.10.B.7, "4-inch HDPE pipe shall have a manufacturing standard of ASTM F 2160 and shall comply with minimum standards as noted above in section B. HDPE Pipe, and shall be SDR 9. 4-inch conduit shall be colored for communications. Color coding shall be permanently co-extruded on pipe outside surface as part of the pipe's manufacturing process. Painting HDPE pipe to accomplish color coding is not permitted. Communication service shall be color coded orange."
6. Ground water is anticipated at elevation minus 6-feet. Contractor is responsible to perform all dewatering operations. Ground water may be discharged into stormdrain system after water has been filtered.
7. Project plans, Sheet 4, Contractor is to maintain vehicle access between building and work area.

8. Section 01100-A-16.2.0.13 Hazardous Waste Removal Certification, The Prime Contractor is required to have a hazardous substance removal certificate or have a listed subcontractor at time of bid that has a hazardous substance removal certificate. If any hazardous materials are discovered, contractor to be compensated per specification section 01250, Add, Potentially contaminated soils may be encountered within the laydown area of station 100+00 Fyffe Avenue. Excavated soils in potentially contaminated soils shall be stockpiled on 12mil plastic with plastic berm and covered until testing is completed. If it is determined that soils profile confirms hazardous contamination, contractor shall be directed on next action to properly dispose of material. Otherwise, soils can be used as backfill or hauled within 2 miles and spread on Port Property.
9. Remove Division II, Sections 02-SITE CONSTRUCTION, 03 – CONCRETE, 05 – METALS, 06 – LUMBER, 07 – THERMAL AND MOISTURE PROTECTION, 09 – FINISHES, 16 – BOLTS, 22 – PLUMBING, 26 – ELECTRICAL, 31 – EARTHWORK, 32 – EXTERIOR IMPROVEMENTS. These sections were inadvertently left in this set of specification.
10. Section 00100-1, paragraph 5. CONTRACT TIME. Work shall be finally and completed within 100 ~~working~~ calendar days [6 days a week] from the date when the Contract Time commences to run.
11. Section 00520-2, paragraph 3.1.1 Contractor shall achieve Final Completion of the entire Work within one hundred (100) ~~working~~ Calendar days [6 days a week] from the date when the Contract Time commences to run as provided in Document 00700 (General Conditions).
12. Remove Section 01100, Special Provisions: Attachment A.
13. Add to Section 01100 Attachment A - TECHNICAL SPECIFICTIONS.

---

## ATTACHMENTS:

- A. Per Directive 2 – 4, Revised Bid Form Document 00400 (4 pages)
- B. Per Directive 13, Section 01100 Attachment A – TECHNICAL SPECIFICATIONS (24 pages)

# RETURN THIS PAGE ONLY

## ACKNOWLEDGMENT OF RECEIPT OF ADDENDUM NO. 1 FOR THE PORT'S AUXILIARY WATER LINE IMPROVEMENTS, CONTRACT NO. 12-22-2

Please sign and return this page only via email to [bids@stocktonport.com](mailto:bids@stocktonport.com) to acknowledge receipt of Addendum No. 1 for this Project consisting of 3 pages plus Attachments listed in 'Attachments' section.

X.....  
Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Printed Name

\_\_\_\_\_  
Company Name

END OF DOCUMENT